

WAAS CH 62917 W27A	APP CRS 272°	Rwy Idg TDZE 839 Apt Elev 842	4000
--	------------------------	---	-------------

RNAV (GPS) RWY 27

VINTON VETERANS MEML AIRPARK (VTI)


RNP APCH-GPS.

▼

When Circling to Rwy 9 at night, operational VGSI required, remain on or above VGSI glidepath until threshold. For uncompensated Baro-VNAV systems, LNAV/VNAV NA below -16°C or above 54°C. Rwy 27 helicopter visibility reduction below ¾ SM NA. When local altimeter setting not received, use Independence altimeter setting: increase LPV DA to 1140 feet, LNAV/VNAV DA to 1374 feet and all visibilities ½ SM; increase all MDAs 60 feet. Baro-VNAV and VDP NA when using Independence altimeter setting.

MISSED APPROACH: Climb to 3000 direct WUZMU and hold.

AWOS-3 120.075	CEDAR RAPIDS APP CON ★ 134.05 266.8	UNICOM 122.8 (CTAF) 0
--------------------------	---	---------------------------------



ELEV 842	TDZE 839
-----------------	-----------------

3000

WUZMU

VGSI and RNAV glidepath not coincident (VGSI Angle 3.00/TCH 32).

CULBE

1.8 NM to RW27

SIFOJ

2500

JOHUU

4 NM Holding Pattern

092°

272°

3000

GP 3.00°

TCH 40

1.2 NM

0.6

3.2 NM

6.1 NM

1.2 NM to RW27

1.440

2500

272°

2500

272°

3000

GP 3.00°

TCH 40

CATEGORY	A	B	C	D
LPV DA	1089-1	250 (300-1)		NA
LNAV/VNAV DA	1323-1¾	484 (500-1¾)		NA
LNAV MDA	1260-1	421 (500-1)		NA
CIRCLING	1320-1 478 (500-1)	1360-1 518 (600-1)		NA